



S.C. Occupational Safety and Health Administration

25 MOST FREQUENTLY CITED CONSTRUCTION STANDARDS

January 1, 2011 - December 31, 2011

| Rank | # Cited | Standard | Hazard Description |
|------|---------|--------------------|--|
| 1 | 50 | 1926.451(g)(4)(i) | Inadequate guardrails on open sides and ends of scaffold platforms |
| 2 | 28 | 1926.405(b)(2) | No covers provided for pull boxes, junction boxes, and fittings |
| 3 | 27 | 1926.602(a)(9)(i) | No audible alarms for material handling equipment |
| 4 | 25 | 1926.300(b)(2) | Unguarded reciprocating, rotating or moving parts of equipment |
| 5 | 25 | 1926.453(b)(2)(v) | No body belt when working from an aerial Lift |
| 6 | 24 | 1926.601(b)(4) | No vehicle shall be operated with an obstructed view |
| 7 | 22 | 1926.501(b)(1) | Fall Protection – unprotected sides and edges/residential construction |
| 8 | 21 | 1926.152(d)(4) | Failed to provide at least one portable fire extinguisher |
| 9 | 20 | 1926.501(b)(10) | No fall protection or employees working above 6 feet in residential construction |
| 10 | 19 | 1926.501(b)(11) | No fall protection for employees working on steep roofs |
| 11 | 19 | 1926.501(b)(13) | No guardrail systems, safety net system, or personal fall arrest system |
| 12 | 17 | 1926.602(a)(9)(ii) | Earthmoving equipment used when the rear view is obstructed |
| 13 | 16 | 1926.152(g)(9) | No signs posted to prohibit smoking near flammable and combustible liquids |
| 14 | 16 | 1926.451(e)(1) | Ladder not provided to access scaffold |
| 15 | 15 | 1926.95(a) | No personal protective equipment |
| 16 | 15 | 1926.404(b) (1) | No ground fault protection used and/or provided |
| 17 | 14 | 1926.405(b) (1) | Unused openings in cabinets, boxes, and fittings not effectively closed |
| 18 | 14 | 1926.701(b) | No guard provided for rebar |
| 19 | 14 | 1926.1053(b)(1) | Ladder side rails do not extend 3 feet above upper surface |
| 20 | 13 | 1926.405(d) | Failed to locate switchboards that have exposed wires Designs of industrial trucks required to meet the American National Standards Institute (ANSI) B56.1-1969 |
| 21 | 12 | 1926.602(c)(1)(vi) | |
| 22 | 11 | 1926.451(b)(1) | Failed to fully plank or deck each platform of the scaffold Failed to erect, move, dismantle, or alter scaffolding under supervision of qualified person |
| 23 | 10 | 1926.451(f)(7) | |
| 24 | 10 | 1926.454(a) | Untrained employees working on scaffolds |
| 25 | 10 | 1926.454(b) | No competent person training when working on scaffolding |