

S.C. Occupational Safety and Health Administration

## 25 MOST FREQUENTLY CITED CONSTRUCTION STANDARDS January 1, 2009- December 31, 2009

| Rank | # Cited | Standard            | Hazard Description   |
|------|---------|---------------------|--|
|      |         |                     |  |
| 1    | 87      | 1926.451(g)(4)      | Guardrail systems not installed to meet requirements   |
| 2    | 60      | 1926.300(b)(2)      | Unguarded reciprocating, rotating or moving parts of equipment   |
| 3    | 46      | 1926.451(e)(1)      | Ladder not provided to access scaffold   |
| 4    | 44      | 1926.453(b)(2)      | Failed to test lift controls, have authorized personnel operate, and stand firmly, on extensible and articulating boom platforms   |
| 5    | 43      | 1926.302(a)(g)(i)   | No audible alarms for material handling equipment  |
| 6    | 41      | 1926.501(b)(10)     | No fall protection for employees working above 6 feet in residential construction<br>No fall protection for employees on walking/working surfaces with unprotected<br>sides and edges 6 feet or more above the lower level |
| 7    | 40      | 1926.501(b)(1)      |  |
| 8    | 39      | 1926.405(b)(2)      | No covers provided for pull boxes, junction boxes, and fittings  |
| 9    | 32      | 1926.602(a)(g)(ii)  | Earthmoving Equipment Used When The Rear View Is Obstructed  |
| 10   | 31      | 1926.1053(b)(1)     | Ladder side rails do not extend 3 feet above upper surface   |
| 11   | 30      | 1926.405(b)(1)      | Unused openings in cabinets, boxes, and fittings not effectively closed  |
| 12   | 28      | 1926.652(a)(1)      | Failed to protect each employee working in an excavation   |
| 13   | 27      | 1926.701(b)         | No guard provided for rebar/protection from impalement   |
| 14   | 26      | 1926.451(b)(1)      | Scaffold not fully planked or decked   |
| 15   | 25      | 1926.95(a)          | No personal protective equipment   |
| 16   | 24      | 1926.602(c)(1)(vi)  | Design of industrial trucks does not meet the requirements of (ANSI) B56.1-1969<br>Failed to use either ground fault circuit interrupters or assured grounding   |
| 17   | 24      | 1926.404(b)(1)(i)   | conductor program  |
| 18   | 22      | 1926.451(g)(1)(vii) | No personal fall arrest or guardrails system while working on scaffolds  |
| 19   | 22      | 1926.501(b)(11)     | No fall protection for employees working on steep roofs  |
| 20   | 18      | 1926.501(b)(13)     | No fall protection for employees engaged in residential construction   |
| 21   | 17      | 1926.405(d)         | Failed to locate switchboards that have exposed wires  |
| 22   | 16      | 1926.100(a)         | Failed to have employees working in hazardous areas wear protective helmets  |
| 23   | 16      | 1926.152(g)(9)      | Failed to post conspicuous and legible signs prohibiting smoking   |
| 24   | 16      | 1926.300(b)(1)      | Failed to equip power operated tools with such guards when in use  |
| 25   | 15      | 1926.501(b)(14)     | Failed to protect each employee working on, at, above, or near wall openings   |