



S.C. Occupational Safety and Health Administration

25 MOST FREQUENTLY CITED CONSTRUCTION STANDARDS

January 1, 2015- December 31, 2015

Rank	# Cited	Standard	Hazard Description
1	39	1.12(a)	Failed to furnish a place of employment free of recognized hazards
2	38	1926.501(b)(1)	Fall Protection – unprotected sides and edges/residential construction
3	23	1910.1200(h)(1)	Inadequate training on hazardous chemicals
4	19	1910.1200(e)(1)	No written Hazard Communication Program
5	19	1910.1200(e)(1)(i)	No list of hazardous chemicals
6	19	1926.152(g)(9)	No signs posted to prohibit smoking near flammable and combustible liquids
7	17	1910.1200(g)(1)	No SDS for hazardous chemicals
8	17	1926.453(b)(2)(v)	No body belt when working from an aerial Lift
9	15	1926.652(a)(1)	No protection from cave-ins for employees in an excavation
10	14	1926.501(b)(1)	Fall Protection – unprotected sides and edges/residential construction
11	14	1910.1200(f)(5)	Containers of hazardous chemicals not properly labeled, tagged, or marked
12	11	1926.451(g)(4)(i)	Inadequate guardrails on open sides and ends of scaffold platforms
13	11	1926.602(a)(9)(ii)	Earthmoving or compacting equipment used when the rear view is obstructed
14	11	1910.178(l)(4)(iii)	No evaluation of forklift operator's performance conducted at least every 3 years
15	10	1926.1053(b)(1)	Side rails on portable ladders not extended at least 3 ft to access upper landing
16	10	1926.651(j)(2)	No protection provided from falling or rolling hazards in excavation
17	10	1926.451(e)(1)	Ladder not provided to access scaffold
18	10	1926.503(a)(1)	No training program for each employee who might be exposed to fall hazards
19	10	1926.602(c)(1)(vi)	Failed to ensure industrial trucks meet the requirements ANSI B56.1-1969
20	9	1926.651(c)(2)	Failed to locate a safe means of egress in trench excavations 4 feet or more
21	9	1926.300(b)(2)	Unguarded reciprocating, rotating or moving parts of equipment
22	8	1926.405(b)(2)	No covers provided for pull boxes, junction boxes, and fittings
23	8	1926.501(b)(13)	No fall protection for employees working above 6 ft in residential construction
24	7	1926.405(b)(1)	Unused openings in cabinets, boxes, and fittings not effectively closed
25	7	1926.602(a)(9)(ii)	Earthmoving or compacting equipment used when the rear view is obstructed

January 1, 2015- December 31, 2015